



Project quotation

Climate & fertigation upgrade

Glasshouse 3

Quotation date	Valid until	Revision
11 September 2026	11 October 2026	R02 · Replaces R01

Prepared for	Delivery site	Prepared by
SYN Riverbend Produce Pty Ltd	SYN Riverbend — Glasshouse 3	Daniel Moss
Alison Reid Operations Manager a.reid@syn-riverbend.example	Lot 14 Murray Valley Highway, Cobram VIC 3644	Estimating estimating@powerplants.example +61 3 0000 0000

Project summary

Supply, delivery, installation and commissioning of a climate control and fertigation upgrade to Glasshouse 3, comprising a replacement controller and irrigation core, environmental sensing, and integration to the existing wireless network.

Total including GST · AUD	Total excluding GST
\$170,023.34	\$154,566.67
	GST component \$15,456.67

Price basis	Lead time
Delivered, installed and commissioned	14–18 weeks from acceptance and deposit
Selected addition	Payment milestones
Root-zone monitoring · Four positions	30% on order · 60% on delivery · 10% on commissioning

This revision replaces SYN-PPO-QUO-000142 R01. The scope, selected options, responsibilities and commercial terms on the following pages form this quotation.



02 / Scope and pricing

Scope and pricing

Equipment and services included in this quotation, with the selected addition shown separately.

All amounts in AUD, excluding GST. Amounts shown are line totals.

#	Description	Quantity	Amount
01	Controller cabinet and core hardware Main control cabinet, power supply, field wiring termination and enclosure.	1 lot	\$33,333.33
02	Environmental sensing package Temperature, relative humidity and CO ₂ sensing across four measurement points.	4 points	\$6,400.00
03	Fertigation unit – four dosing channels Dosing skid, injection assembly, EC and pH monitoring, mixing vessel.	1 lot	\$48,000.00
04	Irrigation valve control Valve interface and field cabling to eight irrigation zones.	8 zones	\$1,866.67
05	Installation Mechanical and electrical installation, on site.	1 lot	\$17,600.00
06	Commissioning and handover training System commissioning, verification against the design basis, and operator handover.	1 lot	\$10,000.00
07	Engineering and documentation Design, drawings, configuration and as-built documentation.	1 lot	\$26,666.67
08	Delivery to site Local delivery to Cobram VIC.	1 lot	\$2,666.67
09	Root-zone monitoring Selected option Four sensing positions, interface and configuration.	1 package	\$12,533.33

Basis of this total

Base equipment and services: \$146,533.34.
Selected monitoring package: \$12,533.33.

The existing customer pump is retained. The weather station and variable speed replacement pump are excluded from this total; see page 3.

Subtotal	\$159,066.67
Project discount	– \$4,500.00
Total ex GST	\$154,566.67
GST (10%)	\$15,456.67
Total incl. GST	\$170,023.34



03 / Technical specification and options

Technical specification

Equipment, configuration and site conditions on which this quotation is based.

Equipment and selected configuration

Control platform	PPO Controller CC-series · Cabinet mounted, 24 V field	
Fertigation unit	F300 – four channel · Skid mounted, pre-plumbed	
Sensing	Temperature, RH, CO ₂ · Four measurement points	
Network	Existing wireless network · Joins network GH-NORTH	
Root-zone monitoring	Substrate moisture, EC and temperature · Four sensing positions · Selected addition	
Irrigation pump	Existing customer pump retained · Installation and commissioning included	
Control points	Irrigation zones	Dosing channels
24	8	4
Growing areas served	Measurement points	Wireless network
2	4	GH-NORTH (existing)

Design basis

Ambient temperature	Priced on the basis that ambient does not exceed 42 °C
Water supply	Priced on the basis of a single mains supply at not less than 250 kPa at the skid
Electrical supply	Priced on the basis of an existing 3-phase supply within 15 m of the cabinet position
Site access	Priced on the basis of unrestricted vehicle access during standard working hours
Network coverage	Priced on the basis that the existing GH-NORTH network reaches the new cabinet position

These are pricing assumptions, not performance commitments. Changes to site conditions require review before acceptance.

Optional additions · Not included in the total

Optional item	Add, ex GST
Weather station Wind, rainfall, outside temperature and light sensing. Mast, sensor head, interface and commissioning.	\$8,666.66
Variable speed replacement pump Variable speed drive, pressure control and controller integration. Replaces the retained customer pump.	\$11,733.33

Pump compatibility and operating requirements require confirmation before issue. An option change requires a revised quotation total.



Commercial terms

Price basis, delivery programme, payment milestones and warranty.

Price basis

Delivered to site, installed and commissioned

Fixed for the validity period stated above. Imported equipment is priced at the exchange rate applying on 11 September 2026; no adjustment applies within the validity period.

Lead time

14–18 weeks

From order acceptance and receipt of deposit.

Excludes periods awaiting customer approval of drawings.

Payment schedule

Milestone	Payment
On order acceptance Deposit — releases procurement	30%
On delivery to site Equipment delivered	60%
On commissioning Practical completion	10%

All amounts payable within 14 days of the relevant invoice.

Warranty

12 months from commissioning.

Parts and labour on equipment supplied by Powerplants Australia.

Exclusions: Consumables, customer-supplied equipment, and damage arising from operation outside the design basis.

Validity and revision

This quotation is valid until **11 October 2026**, for 30 days from issue. Dates use AEST (UTC+10), as recorded in the quotation.

SYN-PPO-QUO-000142 R02 replaces SYN-PPO-QUO-000142 R01. Please use this revision when discussing the scope or returning a response.



Scope responsibilities

Included supply, exclusions and the responsibilities on which the quotation is based.

Included goods

- Controller cabinet, core hardware and field termination
- Fertigation skid with four dosing channels
- Environmental sensing across four measurement points
- Irrigation valve interface for eight zones
- Root-zone monitoring package

Included services

- Mechanical and electrical installation
- Configuration and commissioning
- As-built documentation and operator handover training

Exclusions

Electrical supply upgrade Existing 3-phase supply assessed as adequate; no upgrade allowed for.

Civil works and cabinet plinth By others. Not within Powerplants scope for this site.

Water treatment and filtration Existing filtration retained at the customer's direction.

Customer supplied: existing irrigation pump set. Retained at the customer's direction; installation and commissioning of the retained set are included above.

Customer responsibilities

- Provide safe site access and a clear working area during the installation period.
- Approve drawings within 10 working days of issue.
- Isolate and make safe existing services prior to installation.
- Nominate an operator for handover training.

Assumptions

- Installation carried out in a single continuous mobilisation.
- Existing cable routes are serviceable and reusable.
- Work carried out during standard working hours.

Supporting documents

Referenced files are not included in this sample.

Powerplants Australia — Terms and Conditions of Supply

v4.2

CC-series controller — product specification

v2.1

F300 fertigation unit — manufacturer datasheet

2026-03

Order of precedence: (1) This quotation; (2) the technical specification section of this quotation; (3) attachments, in the order listed.

Manufacturer material describes the product range. Only the configuration set out in this quotation is supplied. Referenced files must accompany an issued quotation.



06 / Review and acceptance

Review and acceptance

Quotation SYN-PPO-QUO-000142 · R02

Please review the customer details, included scope, selected addition and commercial terms together before providing a response.

Quotation summary

- All base equipment and services listed on page 2.
- Root-zone monitoring package, including four sensing positions.
- Existing customer irrigation pump retained.
- Weather station and variable speed replacement pump excluded.

Total ex GST	GST (10%)	Total including GST · AUD
\$154,566.67	\$15,456.67	\$170,023.34

Customer response details

This is a sample signature page for design review. Do not sign or return it as a commercial acceptance.

Customer entity

SYN Riverbend Produce Pty Ltd

Authorised representative's full name

Position

Signature

Date

Email address

Quotation contact

Daniel Moss · Estimating
estimating@powerplants.example

+61 3 0000 0000
Reference: SYN-PPO-QUO-000142 R02

This copy records the selections and amounts shown above. Changes to the scope or options require a revised quotation before a response is accepted. A signed sample is not an order or evidence of delivery.